



### 45' CONCRETE PAVEMENT SECTION TYPICAL CROSS SECTION

NTS

REV: 8/14/18

**NOTES:**

1. TRANSVERSE SAWED CONTRACTION JOINT AT 15' INTERVALS & LONGITUDINAL SAWED CONTRACTION JOINTS AT 11' INTERVALS FOR CONCRETE PAVEMENT.
2. LIME SHALL BE APPLIED AT 6% BY WEIGHT MINIMUM QUANTITY IS 45LBS./SY. IN SOME AREAS A GREATER QUANTITY (OR A LIME SERIES TEST) MAY BE REQUIRED AT THE CITY'S DISCRETION.
3. FOR PI LESS THAN 15, LIME MAY BE OMITTED WITH PRIOR APPROVAL FROM THE CITY.
4. CEMENT SHALL BE APPLIED AT 5% BY WEIGHT. MINIMUM QUANTITY IS 30LBS./SY.
5. SLIP FORM MACHINE WILL BE REQUIRED.



CITY OF ARLINGTON, TEXAS

### 45' CONCRETE PAVEMENT SECTION

DATE:	SCALE: NTS	SHEET ____ OF ____
DESIGNED BY:	DRAWN BY:	CHECKED BY: